



**AURANGABAD MUNICIPAL CORPORATION**  
**FIRE BRIGADE**  
TELEPHONE NO-2334000-40FAX No-2331444

Outward No.AMC/FIRE / **770** /2017

Date 30/08/2017

To,  
Principal,  
Riverdale High School & Canteen Hall Building,  
Gut No. 345, At. Satara Road Satara,  
Aurangabad.

Sub:- Provisional Fire NOC is issued to Principal, Riverdale High School & Canteen Hall Building, Gut No. 345, At. Satara Road Satara, Aurangabad.

Ref:- 1) Your letter dated 29/08/2017  
2) CFO inspection on dated 30/08/2017.

With Reference to the above subject Provisional Fire NOC is issued to the Principal, Riverdale High School & Canteen Hall Building, Gut No. 345, At. Satara Road Satara, Aurangabad. Plot area 44013.00 sq. meter.

3. High School Building B/Up area 1016.00 sq. mtr. Basement + Ground + 02 floors & Height of building 10.00 meter.
4. Canteen Building B/Up area 194.82 sq. mtr. Ground floors & Height of building 5.00 meter.

Owner has paid Capitation fees School Building Rs. 30,000/- Noc fees Rs. 10,000/- & Canteen Building Rs. 20,000/- Noc fees Rs. 10,000/- Total Rs. 65,000/- in Fire brigade Receipt No.108104 dated on 30/09/2017.

Following Fire prevention and Fire protection & Fire Fighting measures subject to the **School Building** shall be provided.

1. Open space all around the building shall be provided for the movement of fire tender and which will carry 25 tons weight capacity.
2. Overhead water tank 10000 lit capacity with the fire pump of suitable capacity for building Shall be provided.
3. Hose reel of 100 feet on all outlets shall be provided.
4. Fire Extinguisher of / Co2/ Soda Acid / Fire Buckets of suitable capacity / quantity shall be provided.
5. All the above requirements shall be carried out with prior approval from fire Brigade.

Following Fire prevention and Fire protection & Fire Fighting measures subject to the **Canteen Building** shall be provided.

1. Open space all around the building shall be provided for the movement of fire tender and which will carry 25 tons weight capacity.
2. Overhead water tank 10000 lit capacity with the fire pump of suitable capacity for building Shall be provided.
3. Fire service inlet 2 way incoming shall be provided.
4. Down comer having outlet on all floors with hose pipe / branch shall be provided.
5. Hose reel of 100 feet on all outlets shall be provided.
6. Fire Extinguisher of / Co2/ Soda Acid / Fire Buckets of suitable capacity / quantity shall be provided.
8. Use of all Pipes of TATA Zenith or APL (APPOLO) or ISI Mark for Fire Down comer system shall be provided
9. All the above requirements shall be carried out with prior approval from fire Brigade.

NOC